

**CLIMADRY**

<b>CONTENTS</b>	<b>PAGE</b>
1. Sequence of operation	1
2. Performance data CD15/20	4
3. Performance data CD30/25	5
4. Electrical data	6
5. Dimensional data Vertical	7,7A
6. Dimensional data Horizontal	8
7. Curb dimensional data	9,9A
8. Typical piping schematic	10,10A
9. Typical wiring schematic	11,11A,11B
10. Model No. Decoder	12

# **CLIMADRY**

## **SEQUENCE OF OPERATION**

May 1, 1997

---

The Climadry is a dual air path air conditioning unit. One air path is dedicated to the conditioning of the fresh air from outside, the second air path is dedicated to the conditioning of the return air from the space (store). The two air paths are mixed together at the inlet of the supply air fan and delivered to the conditioned space.

Climadry has three basic modes of operation as follows :

**DRYOUT Mode**

**CO<sub>2</sub> Mode**

**NORMAL Mode**

A Microprocessor controller, sensing space temperature, space humidity, space CO<sub>2</sub> level, outside air temperature and humidity determines the mode of operation for the unit. DRYOUT mode is considered to be the highest priority to maintain space humidity. CO<sub>2</sub> level gets a second priority. Once the space humidity and CO<sub>2</sub> level is under control, Climadry resumes the Normal mode of operation.

In each mode of operation, microprocessor controls the operation of the compressors and the position of the Return Air (R/A) Bypass damper DA1 and the Outside Air (O/A) damper DA2 as required by specific mode of operation and the space conditions. Climadry incorporates four compressors. Compressor No. 1 and 2 are two speed compressors dedicated to the cooling of the outside air under NORMAL and CO<sub>2</sub> mode and cooling of the portion of the Return Air in DRYOUT mode. Compressor No. 3 and 4 are dedicated to the cooling and heating of the Return Air as required by the space conditions.

### **FAN OPERATION**

Climadry Fan must operate continuously. When Fan start/stop switch is turned on, the controller starts the FAN. A pressure switch sensing differential pressure across the fan provides Fan confirmation to the controller. It is only after the fan confirmation that the unit operation can resume. If the microprocessor fails to confirm the fan operation, all microprocessor outputs are turned off and alarm status is indicated on the display.

### **DRY OUT MODE**

If the space humidity rises above the set point (45%), R/A bypass damper DA1 is fully open , O/A damper DA2 is fully closed. These damper positions shut off the O/A and allow a portion of R/A to circulate over O/A coils. Compressor #1 and #2 are activated in High speed operation. This mode of operation continues until the space humidity falls below the setpoint minus the differential (5%). During DRYOUT if the space temperature falls below the space temperature setpoint, compressor #3 and #4 are activated in heating mode.

**PRELIMINARY**

### **CO<sub>2</sub> MODE**

CO<sub>2</sub> level (ppm) sensor is located in the conditioned space. When CO<sub>2</sub> level rises above the setpoint (1000 ppm), CO<sub>2</sub> mode of operation is initiated provided that the space humidity is under control. In CO<sub>2</sub> mode, O/A Damper starts to open from it's NORMAL(minimum position) setting, allowing more outside air circulation. If CO<sub>2</sub> level continues to rise, the O/A damper continues to open. When CO<sub>2</sub> level reaches the CO<sub>2</sub> setpoint (1000) plus the Proportional Band Setpoint (25), O/A Damper is fully open allowing maximum amount of air to enter through the damper DA2. NORMAL position of the O/A damper DA2 is set by the minimum position potentiometer located in the control box.

R/A Bypass damper DA1 remains closed during CO<sub>2</sub> mode. Operation of Compressor No. 1 and 2 continues to be controlled from the Enthalpy of the outside air as described under NORMAL mode. Operation of Compressor No. 3 and 4 continues to be controlled from the space temperature as described under NORMAL mode.

### **NORMAL MODE**

When space humidity and CO<sub>2</sub> level is under control, Climadry resumes normal mode of operation. In Normal mode O/A damper DA2 assumes a minimum position as set by the minimum position potentiometer to allow design outside air flow to be delivered to the space. R/A bypass damper DA1 remains in the closed position.

#### **Outside Air Cooling**

Microprocessor sensing outside air temperature and humidity calculates the Enthalpy of the outside air. Enthalpy of the outside air dictates the number of cooling stage required for proper cooling of the outside air. There are four stages of O/A cooling operation, achieved by staging the operation of the Compressor No.1 and 2 at Low or High speed. First stage starts Compressor No. 1 at Low speed. Second stage shifts the Compressor No. 1 to High Speed. Third stage starts the compressor No. 2 at Low Speed. Fourth stage shifts compressor No. 2 to High speed.

An averaging temperature sensor located behind the O/A cooling coil provides a feedback data on the temperature of air leaving O/A coil. If this temperature is above 50 Deg. F, the controller forces the operation to the next stage until the O/A leaving temperature drops below 45 Deg F.

Each stage of operation has a minimum run time of 10 minutes and minimum off time of 5 minutes. Each compressor is provided with a high pressure safety switch, low pressure safety switch and compressor motor winding temperature stat. If any of the safety switches open compressor operation is locked out and compressor safety alarm is indicated on the display. Manual reset is required to resume compressor operation.

Compressor #1 and #2 are provided with water regulating valves to maintain proper refrigerant discharge pressure at low and high speed and under varying conditions of loop water temperature. Compressor #2 is provided with a hot gas bypass valve to

protect the coils from freezing under adverse conditions.

#### **Return Air Cooling and Heating**

A temperature sensor mounted in the space provides temperature data to the microprocessor. If the space temperature rises above the set point (75 Deg F) Compressor No. 3 starts on cooling. Further rise in the space temperature starts compressor No. 4 in cooling. If the space temperature drops below the setpoint, mode of operation is shifted to HEATING. Reversing valves are de-energized in heating mode. Compressor No. 3 is started as space temperature falls 1 Deg F below setpoint. Compressor No. 4 is started as space temperature falls 2 Deg F below setpoint.

Each stage of operation has a minimum run time of 10 minutes and minimum off time of 5 minutes. Each compressor circuit is provided with a high pressure safety switch, low pressure safety switch, compressor motor winding temperature stat (10 HP and larger compressors), and water coil freezstat. If any of the safety switches open, compressor operation is locked out and the compressor safety alarm is indicated on the display.

# PERFORMANCE DATA CD15/20

## FRESH AIR PATH

WATER FLOW RATE GPM	FRESH AIR ENT. DB/WB DEG F	LOOP WATER ENT. DEG F	TOTAL COOLING BTUH	SENSIBLE COOLING BTUH	COMPRESOR INPUT WATTS	GROSS EER	HEAT REJECT. BTUH	PRESSURE DROP WATER FT H2O
60	69/75	85	239,286	128,073	17,458	13.7	293,853	26
60	95/75	85	244,700	141,590	17,581	13.8	304,618	26
60	92/77	85	248,842	130,688	17,822	14.1	308,968	26
60	95/79	85	258,579	133,380	17,798	14.5	319,365	26

## RETURN AIR PATH

COOLING									HEATING								
WATER FLOW RATE GPM	RETURN AIR ENT. DB/WB DEG F	LOOP WATER ENT. DEG F	TOTAL COOLING BTUH	SENSIBLE COOLING BTUH	COMPRESOR INPUT WATTS	GROSS EER	HEAT REJECT. BTUH	RETURN AIR ENT. DB DEG F	LOOP WATER ENT. DEG F	TOTAL HEATING BTUH	HEAT OF ABSORP. BTUH	COMPRESSOR INPUT BTUH	POWER INPUT WATTS	COMPRESSOR POWER INPUT WATTS	GROSS COP	GROSS COP	PRESSURE DROP WATER FT H2O
42	75/61	85	177,230	160,949	10,998	16.1	214,756	70	60	189,754	153,396	10,650	5,2	5.2	5.2	12	

NOTE : CAPACITIES, EER AND COP ARE GROSS, FAN MOTOR WATTS , HEAT LOSS OR GAIN IS NOT INCLUDED.

# PRELIMINARY

## PERFORMANCE DATA CD30/25

16-May-97

## FRESH AIR PATH

WATER FLOW RATE GPM	FRESH AIR ENT. DB/WB DEG F	LOOP WATER ENT. DEG F	TOTAL COOLING BTUH	SENSIBLE COOLING BTUH	COMPRESSOR INPUT WATTS	GROSS EER	HEAT REJECT. BTUH	DROP WATER FT H2O	PRESSURE
70	89.75	85	272,683	144,850	22,444	12.2	349,462	28	
70	95.76	85	278,479	181,215	22,552	12.3	355,426	28	
70	92.77	85	278,209	151,429	22,546	12.3	355,136	28	
70	95.79	85	294,454	151,005	22,840	12.0	372,384	28	

## RETURN AIR PATH

COOLING										HEATING				
WATER FLOW RATE GPM	RETURN AIR ENT. DB/WB DEG F	LOOP WATER ENT. DEG F	TOTAL COOLING BTUH	SENSIBLE COOLING BTUH	COMPRESSOR INPUT WATTS	GROSS EER	HEAT REJECT. BTUH	RETURN AIR ENT. DB DEG F	LOOP WATER ENT. DEG F	TOTAL HEATING BTUH	HEAT OF ABSORP. BTUH	COMPRESSOR POWER INPUT BTUH	GROSS COP	PRESSURE DROP WATER FT H2O
84	75.61	85	336,162	254,394	24,758	13.7	422,636	70	60	423,334	326,207	27,880	4.5	12

NOTE : CAPACITIES, EER AND COP ARE GROSS. FAN MOTOR WATTS, HEAT LOSS OR GAIN IS NOT INCLUDED.

# PRELIMINARY

### CLIMADRY SERIES ELECTRICAL DATA

MODEL	POWER SUPPLY V/PH/Hz	COMPRESSOR				BLOWER MOTOR		TOTAL FLA	MIN CKT AMPS	MAX. FUSE*
		QTY	RLA	LRA	HP					
CD15/20H	208-230/3/60	RETURN AIR	2	25	156					
		FRESH AIR LEAD	1	38	222	7.5	23.8	149.8	159	175
		FRESH AIR LAG	1	38	222					
CD15/20F	460-3-60	RETURN AIR	2	12	100					
		FRESH AIR LEAD	1	17.2	95	7.5	10.8	69.2	74	80
		FRESH AIR LAG	1	17.2	95					
CD30/25H	208-230/3/60	RETURN AIR	2	57.2	376					
		FRESH AIR LEAD	1	38	222	10	28	239.7	255	300
		FRESH AIR LAG	1	59.3	320					
CD30/25F	460-3-60	RETURN AIR	2	25.4	142					
		FRESH AIR LEAD	1	17.2	95	10	12.8	106.5	113	125
		FRESH AIR LAG	1	25.7	144					

# PRELIMINARY

NAME: WALL


7

WATER IN/OUT CONN.			
MODEL	REF. AIR CIRCUIT	FRESH AIR CIRCUIT	
CD15/29	2" FPT	2" FPT	
CD30/25	2" FPT	2" FPT	

Clingle Master  
Model No. 69773700  
Front View


FRONT VIEW


LEFT SIDE VIEW



"VERTICAL" UNITS

69773700






## PREFACE


# PRELIMINARY

NAME: KALL  
OBJECT: 69773700-3 DATE: 20-Jan-97 14:55:24




## PRINTING

NAME:WALL 09JECT:69826200\_1 DATE:11-Apr-97 09:51:17




# PRELIMINARY




NOTE: INSULATE SUCTION LINE AND HIGH LINE  
BETWEEN HOB VALVE AND DISTRIBUTOR

EVAP COIL 69774010



**CLIMATEMASTER<sup>®</sup>** 7300 SW 34th  
MI CITY, OK 75140  
REFRIGERANT PIPING  
FRESH AIR SYSTEM COINX/20  
THERMISTOR UNIT 3/5" 1/2" 1" 1-1/2"  
PART NUMBER 69648703

CD 15XX-SYSTEM #3(YELLOW) & #4(GREEN)  
REFRIGERANT PIPING




NOTE: SINGLE CIRCUIT SHOWN. SYSTEM #3 AND #4 ARE SCHEMATICALLY IDENTICAL.



REFRIGERANT PIPING  
RETURN AIR SYSTEM (CD 15XX)

DRAWING #	HEET #
69848402	1
06 JAN 97	




MODEL NUMBER

CLIMADRY MODEL CD 15/20F  
STANDARD UNIT WITH 5:10 HP FAN MOTORDRAWING # 79714401  
4 MAR 97

SHEET # 1 OF 3







உதவு எண்

CLIMADRY MODEL CD 15/20F  
STANDARD UNIT WITH 5:10 HP FAN MOTOR

DRAWING # SHEET #  
79714401 2 OF 3  
4 MAR 97



CLASS CODE: 279



- A=STO  
 B=A1 WTR VALVE (R/A EXT)  
 C=A1 SMOKE DETECTOR (R/AIR & S/AIR)  
 D=A1 SMOKE DETECTOR (R/AIR & S/AIR)  
 E=B1C  
 F=B1D  
 G=WNL-MART STD  
 H=X=SPECIAL  
 I=NONE  
 J=A1 S101 MOTORS/DRY PAC  
 K=X SPECIAL
- 20-25 TON  
 25-25 TON  
 H=208-230V/50Hz/60Hz  
 I=460V/3Ph/60Hz

EXAMPLE:  
CD15/20FAAAHBOA

CLIMATEMASTER® 7300 SW 4th		DECOVER CO. SERIES		CLIMATEMASTER® 7300 SW 4th	
ITEM	ITEM	ITEM	ITEM	ITEM	ITEM
1. CO. NERU [unit]	2. CO. NERU [unit]	3. CO. NERU [unit]	4. CO. NERU [unit]	5. CO. NERU [unit]	6. CO. NERU [unit]
DATE: 01/13/24	DATE: 01/13/24	DATE: 01/13/24	DATE: 01/13/24	DATE: 01/13/24	DATE: 01/13/24
EXPIRATION	EXPIRATION	EXPIRATION	EXPIRATION	EXPIRATION	EXPIRATION

## DESIGN CRITERIA CD SERIES

### RETURN AIR DESIGN CRITERIA

TOTAL COOLING NOM TONS	AIRFLOW RATED CFM	EVAP AIR CFM	BYPASS CFM	ENT AIR DB F	ENT AIR WB F	WATER IN F	WATER OUT F
15	10000	6000	4000	75	61	85	95
20	10000	8000	2000				
30	10000	10000	0				

### OUTSIDE AIR DESIGN CRITERIA

TOTAL COOLING NOM TONS	RATED CFM	ENT AIR DB F	ENT AIR WB F	LVG AIR DB F	WATER IN F	WATER OUT F
20	2500	95	76	45	85	95
25	3100					
30	3700					

EXTERNAL STATIC PRESSURE = 1.0 IWG


STANDARD CONSTRUCTION  
 FARR 30/30 2" FILTERS TO BE STANDARD  
 SINGLE SPEED MOTOR  
 DISCONNECT AND GFI RECEPTACLE  
 ALL DOORS TO BE DOUBLE WALL


OPTIONS :-  
 SMOKE DETECTOR -RETURN AIR  
 SMOKE DETECTOR -SUPPLY AND RETURN AIR

FUTURE OPTIONS :-  
 ELECTRIC HEAT  
 HEAT PUMP HEATING OF OUTSIDE AIR


## CLIMADRY SERIES ELECTRICAL DATA

MODEL	POWER SUPPLY V/PH/HZ	COMPRESSOR				BLOWER MOTOR		TOTAL FLA	MIN CKT AMPS	MAX. FUSE*
		QTY	RLA	LRA	HP	FLA				
CD15/20H	208-230/3/60	RETURN AIR	2	25	156			23.8	149.8	159
		FRESH AIR LEAD	1	38	222	7.5				
CD15/20F	460-3-60	FRESH AIR LAG	1	38	222			100	10.6	175
		RETURN AIR	2	12						
CD30/25H	208-230/3/60	FRESH AIR LEAD	1	17.2	95	7.5		69.2	74	80
		FRESH AIR LAG	1	17.2	95					
CD30/25F	460-3-60	RETURN AIR	2	57.2	376			10	28	300
		FRESH AIR LEAD	1	38	222					
		FRESH AIR LAG	1	59.3	320			10	239.7	255
		RETURN AIR	2	25.4	142					
		FRESH AIR LEAD	1	17.2	95	10		12.8	106.5	113
		FRESH AIR LAG	1	25.7	144					






"VERTICAL" UNITS



LEFT SIDE VIEW



FRONT VIEW

WATER IN/OUT CONN.				
MODEL	RET. AIR CIRCUIT	FRESH AIR CIRCUIT	CLIMATE MASTER	WATER CIRCUIT
CD15120	2" FPT	2" FPT	69773700	1" FPT
CD30125	2" FPT	2" FPT		

